



Knockrabo Phase 2

Planning Stage – Structural Report

October 2021

Waterman Moylan Consulting Engineers Limited Block S, East Point Business Park, Alfie Byrne Road, Dublin D03 H3F4 www.waterman-moylan.ie



Knockrabo Phase 2

Planning Stage – Structural Report

Client Name: Knockrabo Investments DAC

Document Reference: 20-086r.006

Project Number: 20-086

Quality Assurance – Approval Status

This document has been prepared and checked in accordance with Waterman Group's IMS (BS EN ISO 9001: 2015 and BS EN ISO 14001: 2015)

lssue 01	Date 05.02.21	Prepared by R. Nelson	Checked by R. Nelson	Approved by R. Osborne
02	15.10.21	R. Nelson	R. Nelson	R. Nelson
03	28.10.21	R. Nelson	R. Nelson	

Comments

ISSUED FOR PLANNING

Disclaimer:

This report has been prepared by Waterman Moylan, with all reasonable skill, care and diligence within the terms of the Contract with the Client, incorporation of our General Terms and Condition of Business and taking account of the resources devoted to us by agreement with the Client.

We disclaim any responsibility to the Client and others in respect of any matters outside the scope of the above. This report is confidential to the Client and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies on the report at its own risk.

Our Markets







Property & Buildings

Transport & Infrastructure

Energy & Utilities

Environment



Content

1.	Introd	uction	1
	1.1	Scope	1
2.	Site C	onstraints	2
	2.1	Knockrabo Phase 1	2
	2.2	Protected Structures	2
	2.3	Dublin Eastern By-Pass (DEBP)	2
	2.4	Adjacent Residential Properties	2
	2.5	Traffic Management	2
	2.6	Ground Conditions	3
	2.7	Ground Water Table	3
	2.8	Granite Formation	3
3.	Struct	ural Concept	4
	3.1	Substructure	
	3.1.1	Foundations	4
	3.1.2	Retaining Wall Structure	4
	3.1.3	Below Ground Waterproofing	4
	3.2	Super-Structure	5
4.	Susta	inability	6
	4.1	Embodied Carbon	
	4.2	Preliminary Embodied Carbon Assessment	6
5.	Fire P	rotection of the Structure	7
6.	Propo	sed Loadings	8
	6.1	Design Loadings and Service Movements	8
	6.1.1	Vertical Loads	8
	6.1.2	Horizontal Loads	8
	6.1.3	Service Movements	8
	6.1.4	Loading Table	8

Appendices

A. Waterman-Moylan Structure's Drawings

1. Introduction

1.1 Scope

Waterman Moylan has been appointed by Kidac to provide Structural Consultancy Services for the proposed residential development at Knockrabo Phase 2, Mount Anville Road, Dublin 14 and to develop the scheme to Planning Stage.

The following provides a summary of the advice and encapsulates the information gathered thus far.

The main structural issues covered are as follows:-

- Develop an understanding of site constraints.
- Form of the new structure.
- Advise structural dimensions.
- Review of construction methodology in relation to the site constraints
- Optimise building envelope within site constraints.
- Liaised with the other consultants engaged on the project regarding the structural works.

2. Site Constraints

The site of circa 1.78 hectares forms part of a broader site of circa 5.39 hectares on which the construction of Phase 1 has already taken place. Phase 1 to the East of the site comprises a mix of two-storey houses and apartment scheme and was completed in crica 2019.

The subject site occupies the Western side of the broader Knockrabo development and was included as part of the existing grant of planning [D17A/1124]. It is proposed to construct 227 no. residential apartments within four separate blocks (Blocks E, F, G & H) along will associated external communal space and car parking. The site is currently a greenfield site with areas used as allotments, well-established trees and extensive vegetation. The site has a sloping topography that falls from South to North and ranges in level between +76.5mAOD and +58.5mAOD.

The site is relatively constrained with:

- Knockrabo Phase 1
- Protected Structures (Cedar Mount & Gate Lodge)
- Dublin Eastern By-Pass (DEBP)
- Adjacent Residential Properties
- Traffic Management
- Ground Conditions



2.1 Knockrabo Phase 1

Site access and infrastructure services to the site were installed as part of Phase 1. Coordination will be required between the as-built record information and the proposed development.

2.2 Protected Structures

Cedar Mount House and the Gate Lodge lie to the South of the site. These protected buildings will need to be adequately safeguarded from the works to the proposed development.

2.3 Dublin Eastern By-Pass (DEBP)

The proposed Dublin Eastern By-Pass (DEBP) route runs adjacent to the Northern boundary. Following the publication of the DEBP Corridor Protection Study (2011) an access route will be required along the Eastern boundary during construction of the DEBP. Noise attenuation measures and requirements to be considered within the development are outlined in the DEBP Corridor Protection Study (2011).

A noise and vibration assessment with regard to the DEBP has been undertaken and is included as part of this planning application.

2.4 Adjacent Residential Properties

The site is adjacent to several residential properties along Mount Anville Road. Dilapidation surveys will need to be undertaken to these properties ahead of the works commencing, in addition to monitoring of noise and vibration during the works.


2.5 Traffic Management

Construction timings and methods, protection and potential temporary detours for both pedestrians and vehicles shall be studied prior to the commencement of construction activities. The Contractor shall agree and submit proposals to Dun Laoghaire Rathdown County Council for approval.

2.6 Ground Conditions

Geotechnical investigations were carried out on the site by Ground Investigations Ireland in 2019 as part of Knockrabo Phase 1.

The borehole records from the site investigation indicate that shallow granite rock extends across the site and is typically encountered at 2.3m below ground level. The anticipated subsurface geology is likely to be as follows:




2.7 Ground Water Table


Groundwater strikes were noted and ranged between 1.7m and 2.7m (bgl). With regards to the basement waterproofing and consideration in accordance with BS8102:2009 - code of practice for the protection of below ground structures against water from the ground, the water table can be classified as category "high" in accordance with clause 5.1.3.

2.8 Granite Formation

The extent of the shallow granite is shown below. For the majority of the site the proposed building foundations will be kept shallow and will bear directly onto the Weathered Granite formation, that can be excavated using conventional methods for up to 1200mm below the top of this stratum.

To the South of Blocks F, G & H allowance should be made for rock breaking techniques where the Granite Rock formation is shown higher than the proposed Ground Floor levels. To the North of Blocks F, G & H mass concrete lean-mix will be required under footings to achieve a consistent bearing where the Weathered Granite extends to lower levels.





3 Knockrabo Phase 2 Project Number 20-086 Document Reference:20-086r.006

3. Structural Concept

The structural scheme has been arrived upon following the review of a number of design iterations and assessment of floor spans and structural zones.

The scheme presented here aims to:


- Provide a flush soffit (as much as possible), achieving optimal floor sandwich whilst maximising clear floor-to-floor heights.
- Provide a clear path for service routes (as much as possible) •
- Minimise the number column transfers between the ground floor and basement layouts; •
- Avoid ground floor transfer structures through the use of cross-walls acting as deep beams; ٠
- Be capable of fast construction minimising on-site programme time; •

Substructure 3.1

Foundations 3.1.1

From the anticipated soil conditions, it is expected that the structure will be supported on shallow foundations. This will comprise 1200mm thick reinforced concrete strip and pads on mass concrete (leanmix) extending to granite rock or weathered rock formation. To the North of Blocks F, G & H mass concrete lean-mix will be required under footings to achieve a consistent bearing.

The ground floor slabs are 350mm thick reinforced concrete and suspended between the strip and pad footings. The slabs are formed on 50mm T3 Blinding with minimum 225mm T2 hardcore to SR:21 requirements.



3.1.2 Retaining Wall Structure

The Southern perimeter of Blocks F, G & H form a cutting into the sloping site topology. This will require a 300mm thick reinforced concrete retaining wall to uphold the site levels.

The ground floor retaining wall to Blocks F, G & H is approximately 22m from the foundations to Cedar House. This is considered far enough away to allow for an open-cut battered excavation without the need for temporary retention works during construction.

3.1.3 Below Ground Waterproofing

Requirement and details for waterproofing to the below ground elements are shown by the Architect.

Table 2	Grades	of waterproo	fing protection
---------	--------	--------------	-----------------

Gra	ade	Example of use of structure ^{A)}	Performance level
1		Car parking; plant rooms (excluding electrical equipment); workshops	Some seepage and the intended use ^{B)} Local drainage mig
2		Plant rooms and workshops requiring a drier environment (than Grade 1); storage areas	No water penetrati Damp areas tolerat
3		Ventilated residential and commercial areas, including offices, restaurants etc.; leisure centres	No water penetrati Ventilation, dehum necessary, appropri
A)	retail air co	previous edition of this standard referred to ned as its only difference from Grade 3 is th anditioning (see BS 5454 for recommendation tural form for Grade 4 could be the same of	e performance level rel ons for the storage and
B)		age and damp areas for some forms of cons as the ICE's Specification for piling and emb	

Grades of Waterproofing Protection (extract from BS8102:2009)

In habitable areas, core lobbies, electrical rooms and lift-pits, the basement waterproofing performance will need to be BS 8102:2009 Grade 3. Current proposals to achieve this required environment will be developed over the next stage. At this stage and for any preliminary cost plans we would suggest that a "white tank" system by Rascor or Dryteck is considered.

damp areas tolerable, dependent on

ght be necessary to deal with seepage

tion acceptable able; ventilation might be required

tion acceptable midification or air conditioning riate to the intended use


s. However, this grade has not been elated to ventilation, dehumidification or exhibition of archival documents). The

tified by reference to industry standards, s [1].

3.2 Super-Structure


A material options study for the super-structure was undertaken and can be summarised as follows.

	Structural Slab Depth	Framing Layout	Speed-of- Construction	Fire Resistance	Acoustic Performance	Vibration Performance
Hybrid Precast Hollowcore & Crosswalls	275mm	Good	Good	Good	Good-Average	Good
In-situ Concrete Frame	325mm	Good	Poor	Good	Good	Good
Post-tensioned Concrete Frame	250mm	Good	Poor	Good	Good	Good
Steel Frame & Precast Concrete	275mm	Good	Good	Average ¹	Good-Average	Average
Masonry Walls & Precast Concrete	275mm	Poor	Poor	Good	Good-Average	Good
Timber CLT Slabs & Crosswalls	n/a³	n/a ³	Good	Poor ²	Average-Poor	Average




Typical Floor Structural Build-up

Transfers exist at 1st and 6th Floors where the columns layouts are not conductive to the floors below. At 1st Floor the transfer slabs comprise 750mm or 900mm thick reinforced concrete flat slabs with level soffits. At 6th Floor the transfer slabs comprise 300mm hollowcore slabs with a 75mm structural screed.



First Floor & 6th Floor Transfer Slabs

The balconies will be connected to the floor slabs at every level via thermal breaks. The balconies will comprise of either steel frame or in-situ concrete. The balconies may be prefabricated off site and lifted into position.



Typical Balcony Support Detail

5 Knockrabo Phase 2 Project Number 20-086 Document Reference:20-086r.006

1. Additional measures required (intumescent paint/fire boarding/etc))

2. Additional measures required (fire boarding/etc) & early engagement with the local Fire Officer

3. Spans are too great for CLT

It is proposed to use a hybrid precast concrete hollow-core floor slabs with reinforced concrete cross-walls for the superstructure. The structural solution provides economy of design and speed of construction, whilst achieving the Architectural aspirations for minimum transfer structures at Ground Floor.

A hybrid precast concrete and in-situ cross-wall construction has a number of benefits over a conventional concrete frame approach:

- High strength to weight ratio
- Greater opportunity for off-site prefabrication ٠
- Higher quality of finish due to off-site construction •
- Less requirement for temporary works and back-propping slabs .
- Less formwork and shuttering on site •
- Faster construction time on site (early stage first-fix MEP) ٠
- Longer achievable floor spans for shallow floor zone ٠



4. Sustainability

The two main types of carbon impact associated with buildings and infrastructure comprises embodied carbon, which is associated with the locked-up carbon in construction materials, and operational carbon which results from the running of the building's heat, energy and services.

It should be noted that reference to net zero carbon and scoring criteria outlined in BREEAM and LEED typically refer to the building's operational carbon only.

4.1 Embodied Carbon


Waterman-Moylan are committed to minimising the embodied carbon in buildings and raising awareness of the impact design decisions have on the environment. Our design process has adopted the following measures in order to reduce embodied carbon in construction:

- Minimising materials used in construction (efficient sizing of all structural members).
- Avoid transfer structures where possible and if used maximise their efficiencies within the structure. •
- Develop opportunities for off-site prefabrication/construction to minimise material wastage. ٠
- Consider low carbon material substitutes (GGBS, PFA, etc) replacing carbon intensive materials. •
- Seek to repurpose and refurbish existing buildings and/or re-use existing structural elements (existing . foundations, etc).
- Consider the performance of the structure in conjunction with other disciplines (thermal mass, waterproofing performance, etc).
- Considering buildability, installation requirements and follow-on trades to avoid complex details that slows construction and escalates costs.

4.2 Preliminary Embodied Carbon Assessment

Over the Planning Stage, we undertook an initial carbon assessment of the proposed building structure in order to assess the structural scheme against alternative materials. We have developed a simple carbon assessment tool that calculates the carbon of the principle structural materials (steel, concrete, timber, etc) through stages A1-A5 of the BS EN 15978.

MATERIAL	EC (kg/CO ₂ e/m ²)	% Used	
Precast Hollowcore	55	17.5	
Screed (C30/37)	24	7.6	
In-situ Concrete (C32/40)	120	38.1	
Reinforcement	106	33.6	
Steelwork	10	3.2	
TOTAL	315	100	



Embodied Carbon SCORE Rating Scheme (IStructE 2020)

The proposed structural scheme has a higher embodied carbon in comparison to alternative materials. This is primarily due to the carbon intensive production of precast concrete elements and the reluctance by precast manufacturers to use cement replacements (GGBS, PFA, etc).

In-leu of the above, the following measures may be incorporated into the design over the next Stage to reduce the embodied carbon of the proposed structural scheme:

- 1. Further rationalise the transfer structures at Ground Floor and at 6th Floor.
- 2. Incorporate cement replacement GGBS (up to 50% by volume) within the structural screeds, mass concrete, foundations and ground floor slabs.
- Consider an exposed structure where possible in-leu of architectural finishes. 3.
- 4. Consider designing the structural elements for a longer design life of 75 years.
- Optimise the thermal mass of the building's concrete elements for a reduced M&E operational demand. 5.

5. Fire Protection of the Structure

It is currently understood that a 90-minute fire protection will be required generally for the structure, with 120 minutes required for certain core and escape routes, subject to the Fire Consultants Report. 240 minutes is required in electrical ESB substation rooms.

Fire protection to all concrete elements will be achieved as follows, as per IS EN 1992-2:

Core walls and Columns	- RC concrete cover and minimum element dimensions
Horizontal members and hollowcore slabs	- RC concrete cover and minimum element dimensions.
120 minute areas	- RC concrete cover and minimum element dimensions.
240 minute areas	 RC concrete cover and minimum element dimensions.

6. Proposed Loadings

6.1 Design Loadings and Service Movements

6.1.1 Vertical Loads

These comprise superimposed live loads [due to occupancy, plant, storage, etc.], superimposed dead loads [due to M&E services, etc.] and self-weight of structure plus cladding. Superimposed live loads and dead loads are listed below and the design takes into account structure and cladding self-weight.

6.1.2 Horizontal Loads

These comprise either wind loading on the building façade or "notional loads" as defined in British Standards. Notional loads occur due to lack of fit of the structure, etc. The combination of these two are used in the design in accordance with IS EN 1990.

6.1.3 Service Movements

Horizontal and vertical movements due to superimposed live loads and wind loads are limited to the following:

Horizontal building sway [wind load] = $\frac{height}{T}$ 500

Vertical slab/beam deflections [superimposed live load]:

i] Floor beams =
$$\frac{span}{360}$$

ii] Slab/Beam supporting cladding =
$$\frac{span}{500}$$
 or 10 mm whichever is less.

Loading Table 6.1.4

A Typical Bedroom Floor	
200 Precast Slab	3.00 kN/m ²
75mm Screed	1.80 kN/m ²
Floor Finishes	0.35 kN/m ²
Ceiling & Services	<u>0.25 kN/m²</u>
	5.40 kN/m ²

Imposed load (Class A1) 3.0 kN/m² [Including 1.5kN/m² partitions with finishes]

В	B Typical Ground Floor Commercial		
	350 normal weight slab	8.75 kN/m ²	
	Raised floor	0.35 kN/m ²	
	90mm Screed (2000kg/m ³)	1.80 kN/m ²	
	Floor insulation	0.05 kN/m ²	
	Ceiling &services	<u>0.45 kN/m²</u>	
		11.40 kN/m ²	
	imposed load	5 kN/m ²	
D	Roof Areas		
D	200 Precast Slab	3.00 kN/m ²	
	75mm Screed	1.80 kN/m ²	
	Sedum	3.00 kN/m ²	
	Waterproofing	0.30 kN/m ²	
	Insulation	0.20 kN/m ²	
		8.30 kN/m ²	
	imposed load (MEP)	7.5 kN/m ²	
	Imposed load (PVs)	3.0 kN/m ²	
	Access/Maintenance	0.6 kN/m ²	
Е	Corridor / Lobby Areas		
	200 Precast Slab	3.00 kN/m ²	
	75mm Screed	1.80 kN/m ²	
	Floor Finishes	0.35 kN/m ²	
	Ceiling & Services	<u>0.45 kN/m²</u>	
		5.60 kN/m ²	
	Imposed load	5.0 kN/m ²	

Disproportionate Collapse F


> The structure is in excess of five storeys and therefore will be checked for disproportionate collapse in accordance with IS EN 1991-1-7:2006 Annex A and Building Regulations.

Accidental loading at 34 kN/m² will be applied to "key elements", i.e. columns and beams carrying columns, and criteria in regard to perimeter ties and tying forces.





APPENDIX

A. Waterman-Moylan Structure's Drawings




	GENERAL NOTES 1. THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF "WATERMAN MOYLAN" AND IS NOT TO BE COPIED IN WHOLE OR IN PART UNLESS UNDER WRITTEN AGREEMENT. 2. DO NOT SCALE FROM THIS DRAWING. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE ARCHITECT'S AND OTHER DESIGN TEAM'S DRAWINGS AND SPECIFICATIONS		
	LEGEND		
	Denotes 350mm thick RC Ground Floor Slab Allow C32/40 with 170kg/m3 reinforcement (Note - Integrated waterproof concrete additive "Drytech" to be considered in allowances) Denotes outline of transfer slab over (Level 01)		
	Denotes 300mm thick RC Retailing Wall Allow C32/40 with 170kg/m3 reinforcement (Note - Integrated waterproof concrete additive "Drytech" to be considered in allowances)		
()	Denotes 220mm thick RC Wall Allow C32/40 with 200kg/m3 reinforcement (Note - wall achieves 2HR Fire Resistance)		
	Denotes 220x880mm or 220x2000mm RC Blade Column. Allow C50/60 with 220kg/m3 reinforcement		
200	Denotes 350x650mm RC Column Allow C50/60 with 220kg/m3 reinforcement and 25mm Chamfered Corners		
arca. Arrag	Denotes 350x650mm RC Column Allow C32/40 with 150kg/m3 reinforcement and 25mm Chamfered Corners		
	Denotes 100mm thick (7.5N) Blockwork Wall Allow Ancon WP2 Windposts @5m c/c		
arca.	Denotes 1200mm thick RC Strip/Pad Footing Allow C32/40 with 200kg/m3 reinforcement (Note - Mass concrete "leanmix" to Rock)		
	ADDITIONAL NOTES		
	 All stairs to be pre-cast concrete construction Reinforcement densities noted include allowance for laps. Densities to be applied over the gross internal area 		
	including opes Extent of foundations shown subject to site investigation		
am / / / /			
HALI	DRAWING STATUS		
HAU.	ISSUED FOR PLANNING		
	Waterman Moylan Engineering Consultants		
Nº 12	East Point Business Park Dublin D03 H3F4 t +353 1 664 8900		
	info@moylan.ie www.waterman-moylan.ie		
<u> </u>	CLIENT		
	PROJECT Knockrabo Phase 2		
HAL.	TITLE		
	BLOCK G & H		
	LEVEL 0 GA		
1/2	DRAWN DESIGNED CHECKED		
] []	PROJECT DATE SCALE 20-086 26.01.2021 NTS		
172	DRAWING REFERENCE 20-086-WMS-ZZ-ZZ-SK-S-0001		






1. THIS DRAW						
"WATERMAN	 THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF "WATERMAN MOYLAN" AND IS NOT TO BE COPIED IN WHOLE OR IN PART UNLESS UNDER WRITTEN AGREEMENT. 					
	2. DO NOT SCALE FROM THIS DRAWING, WORK TO FIGURED DIMENSIONS ONLY.					
	NG IS TO BE READ IN CONJUN S AND OTHER DESIGN TEAM'S					
SFLOIDEAT						
	LEGEND					
	Denotes 350mm thick RC Allow C32/40 with 170kg/r (Note - Integrated waterpro "Drytech" to be considered	n3 reinforcement pof concrete additive				
	Denotes outline of transfer	slab over (Level 01)				
-	Denotes 300mm thick RC Allow C32/40 with 170kg/r (Note - Integrated waterpre "Drytech" to be considered	n3 reinforcement oof concrete additive				
-	Denotes 220mm thick RC Allow C32/40 with 200kg/r (Note - wall achieves 2HR	n3 reinforcement				
-	Denotes 220x880mm or 2 Column. Allow C50/60 with reinforcement					
	Denotes 350x650mm RC Allow C50/60 with 220kg/r 25mm Chamfered Corners	n3 reinforcement and				
	Denotes 350x650mm RC Allow C32/40 with 150kg/r 25mm Chamfered Corners	n3 reinforcement and				
-	Denotes 100mm thick (7.5 Allow Ancon WP2 Windpo	N) Blockwork Wall sts @5m c/c				
	Allow C32/40 with 200kg/m3 reinforcement (Note - Mass concrete "leanmix" to Rock					
	<u>DNAL NOTES</u> rs to be pre-cast concrete co	nstruction				
- Reinfo	rcement densities noted inclusions of the second states of the second st	ude allowance for laps.				
- Extent	of foundations shown subject	t to site investigation				
DRAWING STA	THE					
	SUED FOR PLAI	NNING				
	Waterman	Moylan				
	Engineering C	consultants				
Eas	st Point Business Park [t +353 1 664 8900	Dublin D03 H3F4				
i	nfo@moylan.ie www.waterman-	moylan.ie				
	KIDAC					
PROJECT	PROJECT Knockrabo Phase 2					
TITLE						
	BLOCK F					
	LEVEL 0 GA					
DRAWN	DRAWN DESIGNED CHECKED					
RN PROJECT						
20-086	DATE 26.01.2021	SCALE NTS				
	DRAWING REFERENCE 20-086-WMS-ZZ-ZZ-SK-S-0008					
20-086	20-086-WWS-ZZ-ZZ-SK-S-0008					



	GENERAL NOTES 1. THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF				
PART UNLES	MOYLAN" AND IS NOT TO BE S UNDER WRITTEN AGREEM LE FROM THIS DRAWING. WC	ENT.			
DIMENSIONS					
	S AND OTHER DESIGN TEAM'S				
	LEGEND				
	Denotes 350mm thick RC	oval 1 Slab			
	Allow C32/40 with 170kg/m	n3 reinforcement			
	Denotes 500mm thick RC Allow C32/40 with 180kg/m	n3 reinforcement			
	Denotes 900mm thick RC Allow C32/40 with 200kg/m				
-	Denotes 220mm thick RC Allow C32/40 with 200kg/m (Note - wall achieves 2HR	n3 reinforcement			
-	Denotes 220x880mm or 22 Column. Allow C50/60 with reinforcement				
=	Denotes Thermal Break (S	chock Isokorb T)			
-	Denotes 203UC46 Cantiler Allow thermal break (Schor all external steelwork to be minimum 85µm	ck Isokorb T-SK) and			
	Denotes 215mm thick (15M	N) Blockwork Wall			
ADDITI	ONAL NOTES				
- All sta	irs to be pre-cast concrete co				
	es to be applied over the gros				
	- Allow 150x300mm deep RC Up-stand to Ground Level Building Envelope (refer to typical details)				
	rus SUED FOR PLAN				
	Waterman	Movlan			
	Engineering C				
Eas	t Point Business Park D	Dublin D03 H3F4			
ir	t +353 1 664 8900 fo@moylan.ie www.waterman-i	moylan.ie			
	IDAC				
PROJECT Knockrabo Phase 2					
	BLOCK F				
	LEVEL 1 GA				
DRAWN					
RN					
PROJECT 20-086	DATE 26.01.2021	scale NTS			
DRAWING REFE	DRAWING REFERENCE				
20-086-WMS-ZZ-ZZ-SK-S-0009					





UK and Ireland Office Locations

